

DATE: 09-08-2020

TEST NUMBER: 0404635

CLIENT	Synthetic Turf Resources
--------	--------------------------

TEST CONDUCTED	ASTM F1551 Water Permeability of Synthetic Turf Systems and Permeable Bases, DIN 18-035
----------------	---



PRODUCT NAME	FLK9
DESCRIPTION OF PRODUCT TESTED	Turf

**GENERAL PRINCIPLE**

The test procedure is used to determine the flow rate of rainfall through a material. A volume of water is poured through the surface and timed. Calculations are then made on the inches of water that would pass through the substrate per hour. The sample was tested as received.

**TEST RESULTS**

IDENTIFICATION	RESULTS
FLK9	3501.40 Inches/Hour
	1.77 Sec/6" Zone
	1141.24 Gal/min/yd <sup>2</sup>

APPROVED BY:

This report is provided for the exclusive use of the client to whom it is addressed. It may be used in its entirety to gain product acceptance from duly constituted authorities. This report applies only to those samples tested and is not necessarily indicative of apparently identical or similar products. This report, or the name of Professional Testing Laboratory Inc. shall not be used under any circumstance in advertising to the general public.